

State of Kansas



15-095-00457-00-01
FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

OCT 19 1964
10-19-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

10-12-64

Dear Sir:

Mr. Thompson of Garvey Drilling Company has this

date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Petroleum Incorporated

Complete Address: 352 W Broadway, Wichita, KANSAS

Lease Name: Greenleaf F Well No. #1

Location: SE-SE Sec. 19 Twp. 28 Rge. 6 (E) (W) W

County Kingman Total Depth 4450 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

252 feet of 8 5/8 inch surface pipe circulated with 150 sacks cement.

Hole filled with heavy drill mud to 250 feet. First cementing plug,

1/4 sack of Hulls, 25 sacks of cement, heavy drill mud to 40 feet.

Second cementing plug, 10 sacks cement to base of cellar. Rat hole

bridged with 2 sacks of cement.

Very truly yours,

Conservation Division Agent