



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co has this  
date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Greenleaf Well No. # 1

Location: C NW NW Sec. 20 Twp. 28 Rge. 6 (E) (W) W

County Kingman Total Depth 4382' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

267' of 8 5/8" surface pipe, cement circulated with 225 sacks.  
Fill hole with drilling mud to 250', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cment with 10  
sack to base of cellar. Bridge and cement rat hole with 2 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

Very truly yours,

FEB 24 1966

Archie Elving  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas