

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -095-20170-0000 (of this well)

Operator's Full Name Halliburton Oil Producing Co. & Comet Pet, Inc.

Complete Address 300 Cameron Bldg., 2915 Classen Blvd, Ok, City, Ok. 73106

Lease Name Koster Well No. 1

Location C. NE-SW Sec. 25 Twp. 28s Rge. 6 (E) (W) X

County Kingman Total Depth 4286

Abandoned Oil Well X Gas Well X Input Well SWD Well D & A

X Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas. 67524 License No. 683

Operation Completed: Hour 12:45 Pm Day 30 Month 3 Year 1979

The above well was plugged as follows:

Plugging started 11-15-1978-250' 8 5/8" casing w/225 sax cement. 4 1/2"
casing set @ 3965' w/150 sax cement. Plug back to 3894'-Top pref, @
3880' Sand back to 3850'. Top sand w/ 4 sax mixed cement w/ dump bailer
Pull 3118' 4 1/2" casing-Mix & pump 25 sax cement in casing-bad casing-
Drill 56' cement out of casing-Howco mixed & pumped 5 sax hulls-20 sax
gel-125 sax 50/50 posmix cement w/2% gel to top of casing-Shut in
w/100# pressure.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the well was plugged as herein stated.

INVOICE # 3-1979

Signed: [Signature]
Well Plugging Supervisor

DATE 4-5-79
CONSERVATION DIVISION
Wichita, Kansas
INV. NO. 9365-W