

15-095-01009-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Blumanhorst Well No. # 1

Location C SE SE Sec. 29 Twp. 28 Rge. 6 (E) (W) W

County Kingman Total Depth 4410'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Mack Oil Company

Address: 812 Union Center Bldg., Wichita, Kansas License No.

Operation Completed: Hour 5:00PM Day 25th Month August Year 1966

The Above well was plugged as follows:

241' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole was
filled with drilling mud to 240', 1st cementing plug, bridged with 1 sack
of Gel-Mud and 1/2 sack of hulls on fluid at 240', and cemented with 35 sacks.
Hole was filled with drilling mud to 60', 2nd cementing plug, bridged with
1 sack of Gel-Mud and 1/2 sack of hulls on fluid at 60', and cemented with
20 sacks. Rat & mouse holes bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audrie Elving
Well Plugging Supervisor

DATE 8/29/66

INV. NO. 3820-W