

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-095-208860000 (of this well)

Operator's Full Name Gear Pet., Co., Inc.

Complete Address 300 Sutton Pl., Wichita, Ks. 67202

Lease Name Trostle Well No. 2

Location E/2 NW SW Sec. 34 Twp 28s Rge. 6 (E) (W) X

County Kingman Total Depth 4061

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12 N. Day 4 Month 9 Year 1980

The above well was plugged as follows:

215' 8 5/8" casing w/200 sax cement. 4 1/2" casing set at 4060' w/125
sax cement. Plug back to 4044'-Preforated at 4026 to 34'-Allied
mixed & pumped in 4 1/2" casing 35 sax common cement to 3600'-Pull
3478' casing-Allied mixed & pumped 8 sax hulls-25 sax gel-125 sax
50/50 posmix cement w/4% gel & 3% cc to top of casing. Shut in w/250#
pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor
STATE CORPORATION COMMISSION

INVOICED
DATE 9-12-80
INV. NO. 3093-w

RECEIVED
SEP - 8 1980
CONSERVATION DIVISION
Wichita, Kansas