

15095-017400000

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Earl F. Wakefield

Complete Address: 515 Union Center, Wichita, Kansas

Lease Name Morehouse "B" Well No. # 1

Location SE NE NE Sec. 20 Twp. 28 Rgs. 5 (E) (W)W

County Kingman Total Depth 3862

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Flint Engineering & Construction Co.

Address: Box 342, El Dorado, Kansas License No. 547

Operation Completed: Hour 2:00PM Day 13th Month Nov. Year 1963

The Above well was plugged as follows:

125' of 8 5/8" surface pipe, cemented to top. 3845' of 5 1/2" long string,
cemented with 50 sacks. Plug back to 3843'. Top perferation 3822'. Bottom
of hole was chatted to 3800', and cemented with 5 sacks. Hole was filled
with mud to 235', 10' rock bridge, cemented with 30 sacks. Hole was filled
with mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.
2975' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/15/63

INV. NO. 8105-W