

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 5 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Maurice L. Brown Trust

Complete Address 1500 Vickers KSB&T Bldg Wichita, KS

Lease Name Moorhouse A Well No. 2

Location NW/SE/NW Sec. 20 Twp. 28 Rge. 5 (E) (W)

County Kingman Total Depth 3890

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Voth Gassing Pulling Co

Address 715 S A Arkansas City, KS License No. 684

Operation Completed: Hour 6:00 PM Day 1 Month 11 Year 1974

The above well was plugged as follows:

278 ft 8 5/8 surface cemented with 200 sacks. 3890 ft 5 1/2 long string
cemented with 100 sacks. Top perf. 3856 ft. Sand to 3800 ft, 5
sacks cement with bailer. Pulled 3160 ft 5 1/2. Set 10 ft rock bridge
at 350 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/22/74
INV. NO. 126-W