

15-095-01061-0000  
KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Icer-Addis  
Complete Address 5307 E Central Wichita, KS  
Lease Name Broadway Well No. 2  
Location SE/NE/NW Sec. 21 Twp. 28 Rge. 5 (E) (W) W  
County Kingman Total Depth 3810  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Art Lamb Casing Pulling Co  
Address 2809 King Hutchinson, KS License No. 440  
Operation Completed: Hour 9:00 AM Day 16 Month 7 Year 1974

The above well was plugged as follows:  
127 ft 8 5/8 surface cemented with 100 sacks. 3805 ft 5 1/2 long string  
cemented with 75 sacks. Open hole. Sand to 3450 ft, 5 sacks cement  
with bailer. Pulled 3330 ft 5 1/2. Set 10 ft rock bridge at 250 ft.  
25 sacks cement. Mud to 40 ft, 10 ft rock bridge, 10 sacks cement  
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed [Signature]  
Well Plugging Supervisor

INVOICED

DATE 7/18/74  
INV. NO. 9546-W