

15-095-01062-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Icer-Addis
Complete Address 5307 E. Central Wichita, KS
Lease Name Broadway Well No. 3
Location NW/SE/NW Sec. 21 Twp. 28 Rge. 5 (E) (W) W
County Kingman Total Depth 3820
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Art Lamb Casing Pulling Co
Address 2809 King Hutchinson KS License No. 440
Operation Completed: Hour 11: AM Day 12 Month 7 Year 1974

The above well was plugged as follows:

127 ft 8 5/8 surface cement circulated. 3817 ft 5 1/2 long cemented with
50 sacks. Open hole. Sand to 3800 ft, 5 sacks cement with bailer.
Pulled 3450 ft 5 1/2. Set 10 ft rock bridge at 240 ft with 25 sacks
cement. Mud to 40 ft, 10 ft rock bridge at 40 ft, 10 sacks cement
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 7/16/74
INV. NO. 9518-W