

15-095-200550000

Form CP-3  
Rev. 6-26-62

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 20 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed December 4, 1967.

Operator's Full Name Dean & Clark, Inc.

Complete Address: 416 Union Center Bldg., Wichita, Kansas 67202

Lease Name Krase Well No. # 1

Location C SL SW NE Sec. 18 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 4000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Dean & Clark, Inc.

Address: 416 Union Center Bldg., Wichita, Ks. 67202 License No. \_\_\_\_\_

Operation Completed: Hour 1:30AM Day 18th Month December Year 1967

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cement circulated with 180 sacks. Hole was  
filled with drilling mud to 225', 1st cementing plug, bridged with 2 sacks  
of dry cement and 1/2 sack of hulls on fluid at 225', and cemented with 23 sacks.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1  
sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with 9  
sacks, with cement from 30' to the base of the cellar. Rat hole bridged and  
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED  
DATE 12/20/67  
INV. NO. 6448-W