

15-095-20055-0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1967
12-20-67
CONSERVATION DIVISION
WICHITA, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed December 4, 1967.

Dear Sir:

Mr. Sunny Jennings of Dean & Clark, Inc. has this
date requested permission to plug the following described well:

Mr. Jennings guarantees payment of the plugging fee.

Operator's full Name: Dean & Clark, Inc.

Complete Address: 416 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Krase Well No. # 1

Location: C 5L SW NE Sec. 18 Twp. 28 Rge. 5 (E)(W) W

County Kingman Total Depth 4000' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jennings was instructed to plug the well as follows:

244' of 8 5/8" surface pipe, cement circulated with 180 sacks. Fill
hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent