


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD 15-095-30044-0000

Kingman County, Sec. 18 Twp. 28S Rge. (E) 5W (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Lario Oil & Gas Company  
Lease Name Clouse Well No. 5  
Office Address 301 S. Market, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 12 19 65  
Application for plugging filed September 14 19 65  
Application for plugging approved September 15 19 65  
Plugging commenced September 12 19 65  
Plugging completed September 12 19 65  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. J. Toman, Holyrood, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3500 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	235.43 Set @	245'
						None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 240'. Pushed plug to 240'. 15 sacks cement through drill pipe. Mud to 50'. Set plug that held Kelly at 50' and cemented to top with 10 sacks. 2 sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 17 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.  
Address El Dorado, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Leo Ross (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo Ross  
301 S. Market, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of September, 19 65

My commission expires July 21, 1966

Frances Leslie Notary Public.

15-095-300440000

LARIO OIL & GAS COMPANY  
Clouse No. 5  
SE SE NW Sec. 18-28-5W  
Kingman County, Kansas

Drilling Commenced: 9-3-65  
Drilling Completed: 9-12-65  
Drilling Contractor: White & Ellis Drilling, Inc.  
Total Depth - 3500' (Driller's)  
I.P. - Dry and Abandoned

CASING RECORD:

7" 235.43 (T.O.) Set @ 245'  
Cem. w/ 110 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Red bed	246
Shale	520
Salt & shale	840
Lime & shale	1025
Lime	1410
Lime & shale	1595
Shale	1935
Shale & lime	2485
Lime	2625
Shale	2675
Lime	2710
Shale & lime	2925
Shale	3045
Lime	3494
Shale	3500

GEOLOGICAL TOPS - ELEC. LOG

Heebner	2764' (-1321')
Brown Lime	3004' (-1560')
Lansing	3044' (-1601')
Base Kansas City	3494' (-2051')
Elec. Log. T.D.	3501'
Driller's T.D.	3500'

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1965  
CONSERVATION DIVISION  
Wichita, Kansas