


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Kingman County. Sec. 19 Twp. 28 Rge. (E) 5 (W)  
Location as "NE/CNW/SW" or footage from lines SW/4 NE/4 NW/4  
Lease Owner Greenland Drilling Company  
Lease Name Viney Well No. 2  
Office Address 506 Union National Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 1-9 1955  
Application for plugging filed 8-10 1956  
Application for plugging approved 8-11 1956  
Plugging commenced 9-1 1956  
Plugging completed 9-5 1956  
Reason for abandonment of well or producing formation Well depleted- not commercial.

If a producing well is abandoned, date of last production August 1956  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Mississippi Depth to top 3839 Bottom 3922 Total Depth of Well 3922 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	178'	None
				5-1/2"	3922'	3241'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into TD 3922'.  
Plugging started 9-1-56. Finished 9-5-56.  
Plugged off bottom with sand to 3818' and dumped 5 sacks cement with bailer and shot 5 1/2" casing at 3400'-3300' and 3234'. Pulled pipe up to 1500' and circulated with 50 sacks mud. Pulled pipe out of hole and plugged well with heavy mud to 175' and set permanent rock bridge. Dumped 20 sacks cement. Filled hole with heavy mud to 35' and mixed 10 sacks for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company  
Address Box 221, Great Bend, Kansas


STATE OF Kansas COUNTY OF Sedgwick, ss.  
Richard S. Davis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*  
Vice-President, 506 Union National Bldg.  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of September, 1956

*[Signature]*  
Notary Public.

My commission expires March 15, 1960



15-095-01053-0000

WELL LOG

COMPANY: GREENLAND DRILLING CO.

Sec. 19 T 28S R 5W  
SW NE NW  
Kingman County, Kansas

FARM: VINEY No. 2

Total Depth: 3922  
Comm: 12-29-54  
Comp: 1-9-55  
Contractor: Greenland Drilling Co.

Casing: 8-5/8" 178'  
5-1/2" 3922'

Elevation: 1437 R.B.

Figures Indicate Bottom of Formations

95	Red rock & clay	TOPS:	
178	Red rock & shale		
475	Shale & lime shells	Brown Lime	3008
800	Shale & shells	Lansing	3028
875	Shale & lime	Miss.	3839
1150	Lime & shale		
1820	Shale & lime		
2110	Shale w/lime streaks		
2275	Shale & lime		
2850	Lime & shale		
3009	Shale		
3012	Lime		
3028	Shale		
3135	Lime		
3310	Lime		
3534	Lime		
3680	Lime & shale		
3837	Shale & Lime		
3865	Lime		
3922	Dolomite		
3922	T.D.		

3028  
1437  
1591

RECORDED  
INDEXED  
APR 11 1955  
KANSAS

STATE OF KANSAS, COUNTY OF SEDEWICK, ss:

I, Richard S. Davis, Vice President of the Greenland Drilling Co., upon oath state that the above and foregoing is a true and correct copy of the log of the Viney #1 well.

Subscribed and sworn to before me this 30th day of April, 1955.

My commission expires March 15, 1956.

Verdina B. Rutledge  
Notary Public

RECORDED  
INDEXED  
APR 19 1955  
PAGE 89