

15-095-01319-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Kingman County, Sec. 19 Twp. 28S Rge. (E) 5 (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Stelbar Oil Corporation, Inc.

Lease Name Kostner Well No. 1

Office Address 310 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 22, 19 60

Application for plugging filed May 22, 19 60

Application for plugging approved May 22, 19 60

Plugging commenced May 22, 19 60

Plugging completed May 22, 19 60

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel

Producing formation Depth to top Bottom Total Depth of Well 3940 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	275'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 240', set plug and dumped 15 sacks mixed cement; filled with mud to 35', set plug and dumped 10 sacks cement, two sacks cement in rat hole. Steel plate welded on surface.

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stelbar Oil Corporation, Inc.

Address 310 Petroleum Bldg., Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Bertrand M. Lester, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein testified and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bertrand M. Lester Jr.

310 Petroleum Bldg., Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1960

Laura Ferguson

Notary Public.

My commission expires January 18, 1964



15-09501319-0000

LOG

Farm: Kostner
Well No. 1
NE NE SW 19-285-SW
Kingman County, Kansas

Owner: Stelbar Oil Corporation, Inc.
Contractor: Stelbar Oil Corporation, Inc.
Drilling Commenced: 5-10-60
Drilling Completed: 5-28-60

8-5/8" 275' cemented with 200 sacks

Elevation: 1458 KB 1455 DF 1452 GR

0	45	Surface clay and sand
45	274	Broken Lime
274	1130	Shale and Shells
1130	1500	Lime and Shale
1500	2680	Shale and Shells
2680	3060	Lime & Shale
3060	3088	Lansing Lime
3088	3537	Lime
3537	3797	Shale and Lime
3797	3915	Shale and Shells
3915	3940	Lime
	3940	RTD

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1960

CONSERVATION DIVISION
Wichita, Kansas