


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec. 19 Twp. 28S Rge. (E) 5 (W)
Location as "NE/CNW/SW" or footage from lines NW SW NE
Lease Owner Stelbar Oil Corporation, Inc.
Lease Name Wyer Well No. 3
Office Address 310 Petroleum Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed July 24, 1960
Application for plugging filed July 24, 1960
Application for plugging approved July 24, 1960
Plugging commenced July 24, 1960
Plugging completed July 24, 1960
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3935 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	268'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 240', dumped 15 sacks cement, set plug and filled with mud to 35', dumped 10 sacks cement, two sacks cement in rat hole, steel plate welded on surface.

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stelbar Oil Corporation, Inc.
Address 310 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bertrand M. Lester, Jr. (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bertrand M. Lester, Jr.
310 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of July, 1960

My commission expires January 18, 1964
Leona Hargrove
Leona Hargrove, Notary Public.



15-095-01320000

LOG

Well No. 3
Farm: Wyer
NW SW NE 19-28S-5W
Kingman County, Kansas

Drilling Commenced: July 12, 1960
Drilling Completed: July 24, 1960
Owner: Stelbar Oil Corporation, Inc.
Contractor: Stelbar Oil Corporation, Inc.

8-5/8" 268' 185 sacks cement 7-12-60

Elevation: 1441 DF 1438 GR.

0	50	Surface Clay, sand
50	220	Broken Lime
220	268	Lime
268	1040	Shale & Shells
1040	1463	Lime & Shale
1463	3016	Shale & Shells
3016	3062	Brown Lime
3062	3520	Lansing, Kansas City Lime
3520	3745	Shale & Lime
3745	3881	Shale
3881	3935	Mississippi Lime
	3935	RTD, D. & A

Drill Stem Test No. 1: July 23, 1960, from 3885 to 3899

Strong blow throughout test, initial shut in time, 30 minutes,
open 1 hr. and 30 min., final shut in time, 30 min.
Recovered 124' of gassy mud, 62' of muddy water.
Gas to surface in 35 minutes, not enough to gauge.

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1960
CONSERVATION DIVISION
Wichita, Kansas