

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15095004570002
API NUMBER

LEASE NAME Greenleaf Trust

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER OWWO #1

SPOT LOCATION SE

SEC. 19 TWP. 28 SRGE. 6W (E) or (W)

COUNTY Kingman

Date Well Completed

Plugging Commenced 9/24/84

Plugging Completed 9/28/84

LEASE OPERATOR TXO Production Corp.

ADDRESS 200 W. Douglas, Suite 300, Wichita, Ks. 67202

PHONE # (316) 265-9441 OPERATORS LICENSE NO. 5171

Character of Well
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 2200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	252'	none
				4 1/2"	2200'	1630'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 35 sacks cement 3% c.c. & plug to 1800'. Shot pipe at 1630'

Pulled 40 joints of pipe. Pumped well with 3 hulls, 6 gel. Had hole in surface

pipe. Ran 300' 2 3/8 tubing, pumped in 2 hulls, 150 sacks cement & circulated

to top of surface, pulled tubing out & put a cap on.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling

License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas

COUNTY OF Rice

ss.

R. Darrell Kelso

(employee of operator) or


(operator) of above-described well, being first duly sworn on oath, says: That

I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 5th day of October, 19 84



My Commission expires:

Notary Public