

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 20 Twp. 28S Rge. (E) 6 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW

Lease Owner Rains & Williamson Oil Co.

Lease Name GREENLEAF Well No. 1

Office Address 1425 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 23 1966

Application for plugging filed February 23 1966

Application for plugging approved February 23 1966


Plugging commenced February 23 1966

Plugging completed February 23 1966

Reason for abandonment of well or producing formation no oil or gas found
in commercial quantities.

If a producing well is abandoned, date of last production - - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4382' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	267'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with rotary mud at 250', set solid bridge and cement with 25 sacks, mud back to 40', set solid bridge and tapped with 10 sacks cement. 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains

1425 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 25th day of February, 1966

Shirley Keck Notary Public.

My commission expires January 8, 1968

1509501005-000

ROTARY DRILLING LOG

OPERATOR: Rains & Williamson Oil Co. and Petroleum, Inc.
 #1 Greenleaf
 C NW NW Section 20-28S-6W
 Kingman County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.
 COMMENCED: 2-8-66
 COMPLETED: 2-23-66
 REMARKS: Set 267' of 8-5/8" surface casing with 225 sacks cement.

FORMATIONS:

Sand & Shells	200°
Red Bed & Shells	267°
Shale	290°
Shells & Shale	1045°
Lime w/Shale	1265°
Lime & Shale	1965°
Shale & Lime	2275°
Lime & Shale	2455°
Shale & Lime	2795°
Lime & Shale	3250°
Lime	3925°
Lime & Chert	3955°
Mississippi	3985°
Chert & Lime	4010°
Cherty Lime	4056°
Lime & Chert	4111°
Lime	4285°
Shale	4350°
Shale & Lime	4382°
Rotary Total Depth (DGA)	4382°

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1966

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 25st day of February, 1966.

My Commission Expires: 1-8-68

Shirley Reck
Shirley Reck, Notary Public