


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-095-20849-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Kingman County, Sec. 27 Twp. 28S Rge. 6 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines
SW SW SE

Lease Owner Graves Drilling Co., Inc.

Lease Name Sowers Well No. 1

Office Address 910 Union Center, Wichita, Kansas 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed July 8, 19 79

Application for plugging filed July 8, 19 79

Application for plugging approved July 8, 19 79

Plugging commenced July 8, 19 79

Plugging completed July 8, 19 79

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4080'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 210'. Pumped 40 sacks of cement through drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40' and pumped 12 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 3 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1979

CONSERVATION DIVISION
Wichita, Kansas
SS.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK
John C. Graves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

John C. Graves

910 Union Center, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of July, 19 79

Betty Brandt

Betty Brandt

Notary Public.

My commission expires May 9, 1983

15-095-20849-0000

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: June 25, 1979
910 Union Center
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: July 8, 1979
910 Union Center
Wichita, Kansas 67202

CASING RECORD: 5 Jts. used 8-5/8" LOCATION: Sowers No. 1
cemented with 200 sacks SW SW SE
Section 27-28S-6W
Kingman County, Kansas

0 - 211 Red bed
211 - 1255 Red bed & shale
1255 - 1519 Shale
1519 - 4015 Shale & lime
4015 - 4055 Chert
4055 - 4080 Chert & lime
4080 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves* President

STATE OF KANSAS)
)
SEDGWICK COUNTY) ss.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1979
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me, a Notary Public, this 12th day of July, 1979.



Betty Brandt
Betty Brandt Notary Public

My commission expires: May 9, 1983