

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 29 Twp. 28 Rge. 6 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SE NE

Lease Owner Beardmore Drilling Company

Lease Name Blumanhourst Well No. 1

Office Address 827 Beacon Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-6 1959

Application for plugging filed 5-6 1959

Application for plugging approved 5-6 1959


Plugging commenced 5-6 1959

Plugging completed 5-6 1959

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4043 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	35'			
Red Beds		35'	259'	8-5/8"	259'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 0 to 40' - 10 sacks cement
- 40' - Wood Plug
- 40' to 190' - Heavy Mud
- 190' to 240' - 18 sacks cement
- 240' - Wood Plug
- 240' to 4043' - Heavy Mud

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1959
CONSERVATION DIVISION
Wichita, Kansas

Note - Also plugged rathole with 1 sack hulls at 8 ft. and 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company

Address 827 Beacon Building, Wichita, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Heber Beardmore*

827 Beacon Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 1959

Leonard P. Tolle

Leonard P. Tolle - Notary Public.

My commission expires January 28, 1960

PLUGGING
FILE SEC. 29 T. 28 R. 6W
BOOK PAGE 45 LINE 18

15-095-00364-0000

BEARDMORE ET AL
Blumanhourst #1
SE NE Sec. 29-28S-6W
Kingman County, Kansas

Drilled By: Beardmore Drilling Company
Drilling Commenced: 4-23-59
Drilling Completed: 5-6-59

Casing Record:

259' of 8 5/8" with 200 sacks cement on 4-25-59

Elevations: KB 1517
DF 1514
Gr 1511

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Shale	35
Red Bed	259
R. B. Shale & shells	800
Shale	970
Anhydrite	1005
Lime & shale	3061
Sand	3133
Lime	3405
Lime & shale	3470
Lime	3588
Lime & shale	3955
Chat	3960
Chert & lime	3993
Lime	4022
Lime & shale	4043
Rotary Total Depth	4043

SCHLUMBERGER TOPS:

Heebner	2922
Douglas	3062
Br. Lime	3174
Lansing	3184
Mississippi Chert	3942

DRILL STEM TEST #1 - 3946-3960 - Shut in 20 min. - Open 1 hour - Shut in 20 min. Recovered 140' muddy salt water. IBHP 1200, FBHP 1035, IF 30, FF 55, Temperature 108°.

STATE OF KANSAS }
COUNTY OF SEDGWICK) ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Handwritten signature of Leonard P. Tolle

Subscribed and sworn to before me this 12th day of May, 1959.

Handwritten signature of Leonard P. Tolle

Leonard P. Tolle - Notary Public

My Commission Expires:
Januray 28, 1960

PLUGGING
FILE SLG 29T 28 6W
BOOK PAGE 45 LINE 18