


15-095-20886000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 34 Twp. 28S Rge. 6W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
E $\frac{1}{2}$ NW SW
Lease Owner Gear Petroleum Co., Inc.
Lease Name Trostle Well No. 2
Office Address 300 Sutton Place, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9-4-80 19
Plugging completed 9-4-80 19
Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owen
Producing formation Depth to top Bottom Total Depth of Well 4061'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	215	None
				4-1/2	4060	3497'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Squeezed hole with 15 sacks gel, 8 sacks hulls and 10 sacks gel. Released plug
and displaced with 125 sacks 50/50 pos, 4% gel and 3% cc.

Plugging Complete

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1980

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 80

Ronald D. Davis
Notary Public.

My commission expires August 25, 1984



OCT 23 1979

DRILLERS LOG

15-095-20886-0000

No. 2 Trostle

CASING RECORD:

COMPANY: Gear Petroleum Company

DESCRIPTION:

8 5/8" @ 215'
w/200 sx cement

CONTRACTOR: Red Tiger Drilling Company

C E/2 NW/4 SW/4
Sec. 34-T28S-R6W
Kingman County, Kansas

4 1/2" @ 4,060'
w/125 sx cement

COMMENCED: October 8, 1979

COMPLETED: October 17, 1979

TOTAL DEPTH: 4,061'

ELEVATION: 1,540' GL

FORMATION	FROM	TO	REMARKS
Surface Soil & Sand	0	15	
Red Bed	15	232	
Red Bed & Shale	232	1025	
Salt, Lime & Shale	1025	1285	
Lime w/Shale	1285	1515	
Lime & Shale	1515	2244	
Lime	2244	2500	
Lime & Shale	2500	2910	
Lime	2910	3020	
Shale & Lime	3020	3274	
Lime	3274	4061	
RTD		4061	


I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 22nd day of October, 1979.

Joyce A. Hagermann
Notary Public



RECEIVED
STATE OF KANSAS COMMISSIONER

OCT 22 1979

CONSERVATION DIVISION
Wichita, Kansas