

2 090022

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,463-6000

W/2 W/2 NE/4
~~S.W. 1/4~~, SEC. 11, T. 28 S, R. 5 W/2

~~1320~~ 3960 feet from W/S section line
2310 feet from NE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5415

Lease Name Brown Well # 3-11

Operator: Tenneco Oil Co.

County Kingman

Name & Address 1010 Milam

Well Total Depth 3886 126.30 feet

Houston, Texas 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300 (950)

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor H-30 Inc. License Number 5107

Address 251 N. Water, Suite 10, Wichita, Ks.

Company to plug at: Hour: 12:00a.m. Day: 14th Month: 7 Year: 19 84

Plugging proposal received from Toman

(company name) K.C.C., Salina, Ks. (phone) _____

were: 50 sacks at 1580'; 50 sacks at 350'; 10 sacks at 40'; 10 in rat; 10 in mouse

RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1984

AUG 02 1984

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by _____

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 12:00a.m. Day: 14th Month: 7th Year: 19 84

ACTUAL PLUGGING REPORT Filled hole with 11 barrells 35 viscosity mud; run drill pipe to 1580'; spotted 50 sacks of cement through drill pipe. Pulled drill pipe to 350'; spotted 50 sacks cement through drill pipe. Pulled remaining drill pipe. Pushed a wood and rubber plug to 40'; circulated 10 sacks cement to surface. Run one joint of drill pipe in rat, circulated 10 sacks cement to surface. Run one joint of drill pipe in mouse hole, circulated 10 sacks of cement to surface.

Remarks: Dowell Ticket #4543

(If additional description is, necessary, use BACK of this form.)

INVOICED

DATE 8-4-84

Signed David W. [Signature]
(TECHNICIAN)

INV. NO. 2858