

To: 1 120841  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-12

API NUMBER 15-047-20,984-0000  
C W/2 SE, SEC. 21, T 24 S, R 18 W/4  
1320 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30208  
Operator: Tri-J Tubulars, Inc.  
Name & Address: 125 N. Market, Ste. 1532  
Wichita, KS 67202

Lease Name Slentz Well # 1-21  
County Edwards 149.17  
Well Total Depth 4590 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 586

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DS&W License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 12 Month: 10 Year: 1993

Plugging proposal received from Flip Phillips  
(company name) Tri-J Tubulars, Inc. (phone) 316-264-1144

were: 4 1/2" at 4589' w/200 sx cement, PBD 4574', Perfs at 4492-99'  
1st plug sand back to 4440' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 125 'sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 15 1993  
Diana Rankin  
(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by \_\_\_\_\_

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11 a.m. Day: 12 Month: 10 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4440' and dumped 4 sx cement on top of sand  
through bailer,  
2nd plug pumped in 8 5/8" with 250 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls,  
released 8 5/8" wiper plug and pumped 125 sx cement. Pumping pressure 0-300 psi and shut in  
vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3202' of 4 1/2" casing.

INVOICED

I (did / did not) observe this plugging.

DATE 11-2-93  
INV. NO. 39090

Signed Diana Rankin  
(TECHNICIAN)