

To: 1 031195 4-6  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,403-0000  
S/2 S/2 SE SEC. 5, T 24 S, R 17 W/E  
440 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5056  
Operator: F.G. Holl Company  
Name & Address: P.O. Box 780167  
Wichita, KS 67278-0167

Lease Name Deckert Well # 1  
County Edwards  
Well Total Depth 4463 145.04 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 6 Month: 4 Year: 19 92

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4460' w/150 sx cement, PBSD 4411', Perfs at 4354-58, 4391-94'  
1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None   
Operations Completed: Hour: 11 a.m. Day: 6 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand  
through bailer,  
2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released  
8 5/8" wiper plug and pumped 125 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1996' of 4 1/2" casing.  
If additional description is necessary, use BACK of this form.  
observe this plugging.

INVOICED  
DATE 5-14-92  
INV. NO. 35243

Signed Steve Durrant (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 1992  
CONSERVATION DIVISION  
Wichita, Kansas