

1-060262

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,182-0000

SE SE NE, SEC. 5, T 24 S, R 17 W/E

2310 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Deckert Well # 2-5

Operator: F. G. Holl

County Edwards

Name & Address 6427 East Kellogg

Well Total Depth 4500 157.50 feet

Wichita, KS 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Co. License Number 5142

Address P. O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 11:00 am Day: 4 Month: July Year: 19 84

Plugging proposal received from Jim Shriner

(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1180' with 50 sx cement

2nd plug at 310' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthis
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:45 pm Day: 4 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1180' with 50 sx cement, 2nd plug at 310' with 50

sx cement, 3rd & 4th plugs -solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED
(If not observed, do not observe this plugging.)

DATE 7-13-84

Signed Paul A. Luthis
(TECHNICIAN)

INV NO. 2468

7-4

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1984
CONSERVATION DIVISION
Wichita, Kansas