

1120569

5-28

233

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,374-0000

CE/25NW SEC. 21, T. 24 S, R. 17 W/E

3300 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Mundhenke Well # 1-21

Operator: FG Holl Company

County Edwards 154.37

Name & Address P.O. Box 780167

Well Total Depth 4750 feet

Wichita, Ks. 67278-0167

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilg. Co License Number 5142

Address Sterling Ks.

Company to plug at: Hour: 1:30 PM Day: 28 Month: 5 Year: 19 91

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilg. Co (phone) _____

1st - Fill Hole @ mud & pump 50sx cement @ 1170'

2nd - Fill Hole @ mud & pump 40sx cement @ 600'

3rd - Fill Hole @ mud & pump 50sx cement @ 350'

4th - Fill Hole @ mud & pump 15sx cement @ 60'

5th - Fill Rat Hole @ 15sx cement

RECEIVED
STATE CORPORATION COMMISSION
JUN 04 1991
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:00 PM Day: 28 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT

1st plug Filled Hole @ mud & pumped 50sx cement @ 1170'

2nd plug Filled Hole @ mud & pumped 40sx cement @ 600'

3rd plug Filled Hole @ mud & pumped 50sx cement @ 350'

4th plug Filled Hole @ mud & pumped 15sx cement @ 60' to bottom of cellar

5th plug Filled ^{Rat} Hole @ 15sx cement

Remarks: Cemented by BJ Services' 60-46-670
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-12-91

INV. NO. 32082

Signed Dan Goodrow
(TECHNICIAN)