

1 080345

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,426 - 0000

SE SE SW, SEC. 13, T 24 S, R 18 (W/TEX)

440 feet from S section line

3080 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name McKinney Well # 1-13

Operator: F. G. Holl

County Edwards 148.98

Name & Address 6427 E. Kellogg, W
Wichita, KS 67207

Well Total Depth 4584 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263 ✓

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 pm Day: 14 Month: March Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4583' PBD 4535 Top swab & jars 4276'
Perfs at 4419.5 - 4420.5'; 4426-4430'

1st plug push plug to 4275' and sand back to 4225' and dump 4 sx cement on top of sand.
through bailer.

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement. Plugging orders by Paul A. Luthi

Plugging Proposal Received by *J. A. [Signature]*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 pm Day: 14 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pushed plug to 4275' and sanded back to 4225' and
dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls,
10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped
an additional 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1985

Maximum pressure 800 psi and shut in 200 psi

Remarks: Recovered 2406' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun
additional description is necessary, use BACK of this form.)

INVOICED

Did / ~~did not~~ observe this plugging.

DATE 3-26-85

INV. NO. 7435

Signed *J. A. [Signature]*
(TECHNICIAN)