

To: 1 030563  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,221-0000

SE NW NW, SEC. 13, T 24 S, R 18 <sup>W/EX</sup>  
4290 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Wolfe Trust Well # 2-13

Operator: F. G. Holl

County Edwards

Name & Address 6427 East Kellogg

Well Total Depth 4611 <sup>149.86</sup> feet

Wichita, KS 67207

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4:00 pm Day: 28 Month: October Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4597' PBD 4577' Perfs at 4420-30', 4455-59-60-62-63-81-82-85-88-90'

1st plug pump 40 sx cement to 4420', 2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:15 pm Day: 28 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 40 sx cement to 4420', 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 50 psi

Remarks: Recovered 2100' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

Signed Steve Quenont (TECHNICIAN)

NOV 1 1985

CONSERVATION DIVISION Wichita Kansas

FORM CP-2/3 Rev. 01-84

INVOICED DATE 11-1-85 INV. NO. 10864