

To: 1 030560  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,545-0000  
C SE SE, SEC. 34, T 24 S, R 17 (W/R)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F. G. Holl  
Name & Address 6427 East Kellogg  
Wichita, KS 67207

660 feet from S section line

660 feet from E section line

Lease Name McKinney Well # 1-34

County Edwards

Well Total Depth 4552 147.94 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 28 Month: October Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4548' PBD 4514' Perfs at 4433-37'

1st plug pump 30sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:35 am Day: 28 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement to bottom, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8"

rubber plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 100 psi

Remarks: Recovered 2573' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.  
STATE CORPORATION COMMISSION

Signed Stew Blument  
(TECHNICIAN)

NOV 1 1985

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 11-1-85  
INV. NO. 10866