

8-22

1 080026

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,174-0000

NW NW SE, SEC. 12, T 24 S, R 18 W/E

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Wolfe Well # 2-12

Operator: F.G. Holl Company

County Edwards 147.84

Name & Address P.O. Box 780167

Well Total Depth 4549 feet

Wichita, KS 67267-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 253'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:40 p.m. Day: 22 Month: 8 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4547' PBTD 4350' Perfs at 3780-3784'

1st plug sand back to 3730' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls and 120 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:21 p.m. Day: 22 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3730' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls and 120 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

RECEIVED STATE CORPORATION COMMISSION

8-28-89

AUG 28 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-30-89

Signed [Signature] (TECHNICIAN)

INV. NO. 25764