

1030162

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,029-0000

SE/4, SEC. 15, T. 24 S, R. 18

660 feet from ~~XX~~/S section line

580 feet from ~~XX~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5021

Lease Name Wheaton Well # 1-15

Operator: Imperial Oil Company
Name & Address 720 Fourth Financial Center
Wichita, KS 67202

County Edwards

Well Total Depth 4561 148.24 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67542

Company to plug at: Hour: 10:30 am Day: 25 Month: April Year: 19 84

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2 set at 4560' PBDT 4450 Perfs at 4306-12 4322-27 4342-46 4373-77

1st plug sand back to 4250' and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 20 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement

Maximum pressure 300# and shut in pressure 150#

Plugging Proposal Received by Steve Demont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00 pm Day: 25 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4560' PBDT 4450 Perfs at 4306-12 22-27 42-46 73-77

1st plug sand back to 4250' and dump 4 sx cement on top of sand, 2nd plug squeeze well with 3 sx hulls, 20 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement.

Maximum pressure 300# and shut in pressure 150#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton. They recovered 3490' of 4 1/2" (if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 5-4-84

MAY 03 1984

Signed Steve Demont
(TECHNICIAN)

INV. NO. 1387

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84