

10-3

To: 1 120145  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,281-0000  
C SW SE, SEC. 16, T 24 S, R 18 W  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056  
Operator: F.G. Holl Company  
Name & Address: P.O. Box 780167  
Wichita, KS 67207

Lease Name Wheaton Well # 1-16  
County Edwards 151.58  
Well Total Depth 4664 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor: Kelso Casing Pulling, Inc. License Number 6050

Address: Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 3 Month: 10 Year: 19 88

Plugging proposal received from Millard Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4658' PBSD 4450' Perfs at 4322-30'

1st plug sanded back to 4275' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

10-7-1988

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operation started: Hour: 4:30 p.m. Day: 3 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 3100' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 10-10-88

Signed *Dean Rankin* (TECHNICIAN)

INV. NO. 22560