

1 010228

MAR 3 1 1987

137

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C W/2 SW NE, SEC. 3, T 24 S, R 17 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,279-0000

3300 feet from S section line

2310 feet from E section line

Lease Name F. Massey Well # 3-3

County Edwards 144.63

Well Total Depth 4450 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 309

Operator License # 5056

Operator: F.G. Holl Estate

Name & Address P.O. Box 780167

Wichita, KS 67278-0167

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Company License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 9 a.m. Day: 21 Month: 3 Year: 19 87

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1158'

1st plug at 1140' with 50 sx cement, 2nd plug at 570' with 50 sx cement,

3rd plug at 330' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 a.m. Day: 21 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1170' with 50 sx cement,

2nd plug at 570' with 50 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

MAR 26 1987

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. (If additional description is necessary, use BACK of this form.)

INVOICED (If back (add) not) observe this plugging.

DATE 3-27-87

16446

Signed Jack Luthi (TECHNICIAN)