

1 040184

11-14

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,329-0000

NW NW SW, SEC. 3, T 24 S, R 17 W/EX

2310 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Hammeke Well # 6-3

Operator: F.G. Holl Company

County Edwards 148.04

Name & Address P.O. Box 780167

Well Total Depth 4555 feet

Wichita, KS 67278-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Company License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 2:10 a.m. Day: 14 Month: 11 Year: 19 88

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-3727

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2109' KB
Anhydrite 1125-48'

1st plug at base Anhydrite with 50 sx cement, 2nd plug at 1/2 anhydrite with 40 sx cement,

3rd plug at 300+' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:10 a.m. Day: 14 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1180' with 50 sx cement,

2nd plug at 600' with 40 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 11-21-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 23039