

1 020326

8-16

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,361-0000

SW SW NW, SEC. 3, T 24 S, R 17 W/E

2970 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name R. Massey Well # 4-3

Operator: F.G. Holl Company

County Edwards 144.62

Name & Address P.O. Box 780167

Well Total Depth 4450 feet

Wichita, KS 67278-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Company License Number 5142

Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 4:30 a.m. Day: 16 Month: 8 Year: 1990

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1129-46'

1st plug at 1150' with 50 sx cement, 2nd plug at 600' with 40 sx cement,

3rd plug at 330' with 50 sx cement, 4th plug at 60' with 15 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 a.m. Day: 16 Month: 8 Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 1170' with 50 sx cement,

2nd plug at 580' with 40 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 60' with 15 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (XXX) do not observe this plugging.

DATE: 8-21-90

Signed Glenn L. Barlow (TECHNICIAN)

INV. NO. 29073