

To: 1 121056. 7-27 00487
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION NW NW SW, SEC. 10, T 25 S, R 14 W/E
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4419
Operator: Bear Petroleum, Inc.
Name:
Address P.O. Box 438
Haysville, KS 67060

2310 feet from S section line
4950 feet from E section line
Lease Name Neelands Well # 1
County Stafford 134.42
Well Total Depth 4136 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Gressel Oil Field Service, Inc.
License Number 3004
Address P.O. Box 607, Burrton; KS 67020

Company to plug at: Hour: 9:30 a.m. Day: 27 Month: 7 Year: 19 95

Plugging proposal received from Dick Schremmer

(company name) Bear Petroleum, Inc. (phone) 316-524-1225

Notes: 4 1/2" at 4136' w/150 sx cement, PBD 4100', Perfs at 4072-84, 3818-23, 3850-52, 3856-60'

1st plug set CIBP above 3818' and dump 2 sx cement on top,

2nd plug pump in 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:30 a.m. Day: 27 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3818' and dumped 2 sx cement on top with bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released wiper plug and pumped 115 sx cement.

Pumping pressure 0-500 psi and shut in 0 psi.

Plug container blew out while pumping final cement. Had 115 sx cement in lost approx. 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1886' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and agree to observe this plugging.

DATE AUG 02 1995

Signed Duane Barker
(TECHNICIAN)

INV. NO. 43227
7-27