

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,279-0000

LEASE NAME F. Massey

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3-3

3300 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 3 TWP. 24 SRGE. 17 (E)(W)

COUNTY Edwards

Date Well Completed 3-21-87

Plugging Commenced 9:45 AM

Plugging Completed 11:00 AM

LEASE OPERATOR F. G. Holl Estate

ADDRESS P. O. Box 780167
Wichita, Kansas 67

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Dry Hole

(Oil, Gas, D&A SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	309'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. 50 sacks at 1170; 50 sacks at 570; 50 sacks at 330';
10 sacks 0 - 40'. Used 60/40 Pozmix, 6% gel. 15 sacks in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. WUELLNER

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STERLING DRILLING COMPANY

(Signature) [Signature]
F. A. Wuellner, Secretary

(Address) P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 87

[Signature]
Agnes D. Wurst, Notary Public

My Commission Expires: 4-6-89



MAR 27 1987

Form CP-4
Revised 07-86

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - F. MASSEY #3-3

Located: C W/2 SW/4 NE/4, Section 3-24S-17W, Edwards
County, Kansas

OWNER: F. G. Holl Estate

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 14, 1987

COMPLETED: March 21, 1987

TOTAL DEPTH 4450'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 310 Shale, Sand, Red Beds	Ran 7 joints 8 5/8" casing. 300.86' set at 309' K.B. Cemented with 200 sacks 60/40 Pozmix, 2% gel, 3% cc.
310 - 1130 Shale	Plug down at 10:30 PM, 3-14-87, by B. J. Titan.
1130 - 1151 Anhydrite	
1151 - 4450 Lime and Shale	Plugged.

Deviation Surveys: 1/2° at 300'
1° at 2085'
2 1/4° at 4332'

MAR 27 1987