

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,329-0000

LEASE NAME Hammeke

WELL NUMBER #6-3

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 3 TWP. 24S RGE. 17 (N) or (W)

COUNTY Edwards

LEASE OPERATOR F. G. Holl Company

ADDRESS P.O. Box 780167, Wichita, KS 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed 11/14/88

Character of Well D & A

Plugging Commenced 10:15 PM

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/13/88

3:00 AM

The plugging proposal was approved on 11/14/88 (date)

by Steve Pfeiffer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS AND WATER RECORDS

CASING RECORD

Form	Content	From	To	Size	Put In	Pulled out
	<u>11-16-88</u>			<u>8 5/8"</u>	<u>290.12'</u>	<u>None</u>

Describe the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Filled hole with heavy mud. 50 sacks at 1180'; 40 sacks at 600';
50 sacks at 330'; 10 sacks 0 to 40' and 15 sacks in rathole.
Used 60/40 Pozmix with 6% Gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P.O. Box 129, Sterling, KS 67579

STATE OF Kansas COUNTY OF Rice, ss.

F. A. Wuellner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F. A. Wuellner

F. A. Wuellner, Secretary

(Address) P.O. Box 129, Sterling, KS 67579

SUBSCRIBED AND SWORN TO before me this 14th day of November, 19 88



My Commission Expires: 4/6/89 Agnes D. Wurst

Agnes D. Wurst Notary Public

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- Hammeke #6-3
 Located NW NW SW, Sec. 3-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl Company
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 7, 1988
 COMPLETED: November 14, 1988

TOTAL DEPTH: 4455'

LOG

CASING RECORD

0 - 70	Surface Soil & Sand	Ran 7 joints of 8 5/8" 25# casing. 290.12' set at 302' KB. Cemented with 225 sacks 60/40 Pozmix, 2% Gel, 3% cc. Plug down at 5:15 PM by BJ Titan. Good returns.
70 - 740	Redbeds & Shale	
740 - 1125	Shale	
1125 - 1470	Anhydrite	
1470 - 4455	Shale & Lime	Plugged.

Deviation Survey: 3/4° at 4,308'

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 16 1988
 CONSERVATION DIVISION
 Wichita, Kansas