


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 19 Twp. 28 Rge. 7 (W)
Location as "NE/CNW/SW" or footage from lines 150' West of C NW SW
Lease Owner: Stelbar Oil Corporation, Inc.
Lease Name: Henning 'A' Well No. 1
Office Address: 310 Petroleum Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 29, 1965
Application for plugging filed May 6, 1965
Application for plugging approved April 30, 1965
Plugging commenced April 29, 1965
Plugging completed April 29, 1965
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving
Producing formation Depth to top Bottom Total Depth of Well 4463 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled with mud to 260'. Bottom plug set at 260' with 25 sacks cement.
Mud to 40'. Top plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1965
5-7-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor S & S Drilling Co.
Address Box 645, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Bertrand M. Lester, Jr. (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Bertrand M. Lester, Jr.*
310 Petroleum Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1965.

My commission expires May 7, 1966.

Talia Zuhars
Talia Zuhars Notary Public.

WELL LOC
 Hennin #A1
 C NW SW 19 28-7
 Kingman County Kansas

15-095-30024-0000

FROM	TO		Elevation	1649 KH
0	280	Sand Shale & Lime		
280	650	Red Bed		
650	1610	Shale & Shells	<u>Formation Tops</u>	
1610	1830	Lime		
1830	2830	Shale & Lime	Brown Lime	3359
2830	3375	Lime	Lansing K.C.	3371
3375	3417	Shale & Lime	Swore	3737
3417	3838	Lime	Hutha	3776
3838	3857	Lime & Shale	BKC	3938
3857	4061	Lime	Cerokee	3974
4061	4307	Lime & Chert	Mississippi	4068
4307	4443	Shale	Kinderhook	4308
4443	4459	Lime	Chattanooga	4409
4459	4463	Sand	Viola	4449
4463		Total depth	Simson	4459

STATE OF KANSAS

COUNTY OF BARTON ss

T.D. Sweetman, member of S & B Drilling Company,
 being first duly sworn on oath says: that he has knowledge of the facts,
 statements and matters herein contained and the log of the above described
 well as filed and that the same are true and correct.

T.D. Sweetman

Subscribed and sworn before me this 4th day of May, 1966.

[Signature]

Notary Public Barton County

My Commission Expires April 24, 1967