


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 P. O. BOX 17027
 WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Hodgeman County. Sec. 3 Twp. 24S Rge. (E) 21 (W)
 Location as "NE/CNW/SE/4" or footage from lines C NE/4
 Lease Owner RICHARD R. HORNER
 Lease Name M. Gleason Well No. 1
 Office Address 440 N. St. Francis, Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 1-23 19 75
 Application for plugging filed 1-23 19 75
 Application for plugging approved 1-23 19 75
 Plugging commenced 1-23 19 75
 Plugging completed 1-23 19 75
 Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.
 If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4677 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	293	8-5/8"	285	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 850', plug, 60 sx cement;
 Fluid to 550', plug, 35 sx cement;
 Fluid to 40', plug, 10 sx cement;
 Two sacks cement in rat hole.

Name of Plugging Contractor D N B DRILLING, INC. (If additional lines are required, use BACK of this sheet)
 Address 701 First National Building
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Ks.
 (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 75

My commission expires August 25, 1976

Ella Priess
 Ella Priess Notary Public.

Ella Priess
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Com. Expires Aug. 25, 1976

DRILLERS' LOG

RICHARD R. HORNER
 No. 1 M. Gleason
 C NE/4, Sec. 3-24S-21W
 Hodgeman County, Kansas

Elev: 2347 K.B.

Commenced: 1-14-75
 Completed: 1-23-75

Surface Casing: 285' of
 8-5/8" cemented w/235 sx
 common cement, 2% Gel, 3% cc.
 1-14-75

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 293
Shale	293 - 834
Blaine Anhydrite	834 - 841
Sand & Shale	841 - 1030
Shale	1030 - 1150
Red Bed & Shale	1150 - 1443
Anhydrite	1443 - 1460
Red Bed, Sand & Shale	1460 - 1805
Shale	1805 - 2280
Lime & Shale	2280 - 3390
Shale & Lime	3390 - 3595
Lime & Shale	3595 - 4055
Lime	4055 - 4677 T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 29 1975
 CONSERVATION DIVISION
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 27th day of January, 1975.

My Commission Expires:
 August 25, 1976

Ella Priess
 Ella Priess, Notary Public

Ella Priess
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Com. Expires Aug. 25, 1976