

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 6 Twp. 24S Rge. xxx 21 (E) (W)

Location as "NE/CNW/SW" or footage from lines
Lease Owner: Pickrell Drilling Company
Lease Name: Offerle "B" Well No. 1
Office Address: 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 28 19 69
Application for plugging filed June 28 19 69
Application for plugging approved June 28 19 69
Plugging commenced June 28 19 69
Plugging completed June 28 19 69
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4610 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	277'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug 900', 80 sacks cement. Plug @ 270', 30 sacks
cement. Plug @ 45' w/15 sacks cement.


RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 3rd day of July 19 69



L. M. Whiting
Notary Public.

My commission expires May 10, 1970

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 4th National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 6/16/69

Rotary Drilling Completed 6/28/69

LOCATION: Offerle "B" # 1, C NE NW Sec. 6-24S-21W
Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD:

Ran 7 jts. used 28# 8-5/8" casing set @ 277' KB, cemented with 170 sacks cement. Circulated. Completed @ 9:45 PM June 16, 1969.
No oil string run. D & A Plugged June 28, 1969.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Clay & Post Rock
135	Shale & Sand
315	Shale
335	Sand
575	Shale
700	Red Beds
725	Blain
900	Shale - Red Beds
1050	Sand
1410	Shale & Shells
1445	Anhydrite
1500	Shale & Shells
1965	Shale
2310	Shale - Lime
2585	Lime & Shale
2870	Lime
3000	Lime - Shale
3190	Shale & Lime
3580	Lime & Shale
3685	Lime
3910	Lime & Shale
4555	Lime
4610	Lime & Dolomite & RTD

C.F.S.

4350
4343
4385
4413
4425
4430
4530
4585
4610

S.L.M.

Strap	3694.27
Board	3693.50
	<u>.77 Short</u>

Slope Tests

2000
2500
3000
3500
4000
4500

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1969
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 10 day of July, 19 69, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting
L. M. Whiting Notary Public

