

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 19 TWP. 24S RGE. 21 E/W
Location as in quarters or footage from lines:
NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner PETX Petroleum Corporation
Lease Name Cole Well No. 1
Office Address 1616 Glenn Arm Place, Suite 1804, Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed March 26, 1981
Application for plugging filed Verbal Application
Plugging commenced March 26, 1981
Plugging completed March 26, 1981
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor

Producing formation _____ Depth to top _____ bottom _____ T.D. 4810'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	327'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4810' (rotary total depth) to 920'. Set plug at 920' and cemented with 60 sacks cement. Filled hole with heavy rotary mud from 920' to 330' and cemented with 25 sacks. Filled hole with heavy rotary mud from 330' to 40'. Set solid plug at 40' and cemented cellar with 40 sacks cement and 15 sacks hulls, 5 sacks in rat hole.

4-14-81

Plugging operations accomplished utilizing Sun Oil Well Cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED
CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing Company
Box 169, Great Bend, KS 67530

APR 14 1981

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger, Agent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) [Signature]
251 N. Water, Suite 10, Wichita, KS
(Address) 67202



SUBSCRIBED AND SWORN TO before me this 10th day of April, 19 81

Elsie Willison
Notary Public.

My Commission expires: July 25, 1982

KANSAS DRILLERS LOG

COMPANY PETX Petroleum Corporation

SEC. 19 T. 24S R. 21W
LOC. NW SE

FARM Cole

NO. 1

ROTARY TOTAL DEPTH 4810'

COUNTY Hodgeman

COMM. March 18, 1981

COMP. March 26, 1981

CONTRACTOR H-30, Inc.

ISSUED December 9, 1981

CASING

10 3/4"

8 5/8" set at 327' with 250 sacks

ELEVATION 2343' gr.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	960'
Dakota Sand	1029'
Shale	1478'
Anhydrite	1491'
Shale	2403'
Shale and Lime	2765'
Lime and Shale	2965'
Shale & Lime	3380'
Lime and Shale	3600'
Shale and Lime	3820'
Lime and Shale	3968'
Lime	4774'
Mississippi	4810'
Rotary Total Depth	4810'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

Sate of Kansas)
County of Sedgwick) ss.

Subscribed and Sworn to before me, a Notary Public, in and for said county and state this 8th day of April, 1981.

Elsie Willison
Elsie Willison - Notary Public

My appointment expires:

July 25, 1982

RECEIVED
STATE NOTARY COMMISSION
APR 14 1981
CONSERVATION DIVISION
Wichita, Kansas