

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 10 Twp. 25 Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE NE NE

Lease Owner White Eagle Oil Company

Lease Name Toland Well No. 3

Office Address First National Building, Tulsa 3, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 6, 19 53

Application for plugging filed September 6 19 53

Application for plugging approved September 6 19 53

Plugging commenced September 6 19 53

Plugging completed September 6 19 53

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Viola Depth to top Bottom Total Depth of Well 4210 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	862	8 5/8	862	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy rotary mud from 4210 T.D. to 300 ft. Plug set at 300 ft. hole filled with 20 sacks cement; top plug set at 40 ft. hole filled with 10 sacks cement to surface.

9-12-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hilton Drilling Company, Inc.

Address P. O. Box 108, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Henry Peacock, Secretary (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock Secretary

P. O. Box 108, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 53

My commission expires April 4, 1956.

Margaret Whitman Notary Public.

PLUGGING
FILE SEC 10 T 25 R 14W
BOOK PAGE 127 LINE 16

D R I L L E R ' S L O G

COMPANY: WHITE EAGLE OIL COMPANY
 CONTRACTOR: HILTON DRILLING COMPANY, INC.
 FARM NAME: TOLAND NO. 3
 COMMENCED: 8-22-53
 COMPLETED: 9-6-53

LOCATION: SE NE NE
 Sec. 10-25-14
 Stafford County
 Kansas
 ELEVATION: 1961 K.B.


Casing Used: 8 5/8" set at 859' w/500 sx.

Sand and Clay	110
Shale	220
Shale, Red Bed, and Shells	500
Red Bed	850
Chalk	856
Anhydrite	880
Shale and Shells	990
Red Bed and Shale	1200
Shale and Shells	1380
Shale and Salt	1560
Shale and Lime Shells	1670
Shale and Broken Lime	1920
Broken Lime	2165
Shale and Shells	2200
Shale and Broken Lime	2325
Shale and Lime	2415
Broken Lime	2475
Shale and Shells	2615
Shale, Lime and Shells	2805
Shale and Lime	2965
Lime	3005
Lime and Shale	3180
Broken Lime	3300
Lime and Shale	3362
Broken Lime	3390
Lime	3442
Lime and Shale	3585
Lime	3981
Lime and Shale	4022
Lime, Chert, and Shale	4171
Viola Lime and Chert	4176
Lime, Chert, and Shale	4204
Lime	4210
Total Depth	4210

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 13 1953
 CONSERVATION DIVISION
 Topeka, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.



HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 8th day of September, 1953.

My commission expires April 4, 1956.

Margaret Whitman
 Notary Public