


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

STAFFORD County, Sec. 10 Twp. 25S Rge. 14W (X) X(W)
Location as "NE/CNWxSWx" or footage from lines N/2 NE SW
Lease Owner PETROLEUM, INC.
Lease Name NEELANDS Well No. 2
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MAY 8 19 61
Application for plugging filed MAY 8 19 61
Application for plugging approved MAY 8 19 61
Plugging commenced MAY 8 19 61
Plugging completed MAY 8 19 61
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT P. TOMAN
Producing formation - - - - - Depth to top - - - Bottom - - - Total Depth of Well 3734 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	293'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - - - feet to - - - feet for each plug set.

MUDDING UP WITH HEAVY MUD TO 280' FOLLOWED BY WOODEN PLUG AND 1/4 SACK HULLS. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ON TO HULLS. MUDDING UP WITH HEAVY MUD TO 35' FOLLOWED BY WOODEN PLUG 1/4 SACK HULLS AND 10 SACKS CEMENT TO BASE OF WELL CELLAR. 2 SACKS CEMENT IN RAT HOLE.

5-26-61
RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (XXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 24TH day of MAY, 1961

Arthur J. Miles
Notary Public.

My commission expires APRIL 14, 1963



WELL LOG

COMPANY PETROLEUM, INCORPORATED

FARM NEELANDS

NO. 2

SEC. 10 T. 25S R. 14W

LOC. N/2, NE, SW

TOTAL DEPTH 3734'


COUNTY STAFFORD CO., KANSAS

COMM. May 2, 1961

COMP. May 8, 1961

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8-5/8" @293' w/225 sax.



ELEVATION 1962' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

125	Surface sand
230	Shale
750	Red bed
800	Sand
865	Shale & shells
875	Anhydrite
1760	Red bed, shale & shells
1900	Shale & lime streaks
2005	Lime & shale
2200	Lime
2220	Shale & lime
2400	Lime
2765	Shale & lime
3485	Lime & shale
3538	Lime
3719	Lime & shale
3734	Lime
3734	T. D.

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1961

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS

County of BARTON

SS

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #2 NEELANDS well.

Subscribed and sworn to before me this 23rd day of May 19 61

My Commission Expires April 14, 1963

Verne A. Morris

Arthur J. Mule
NOTARY PUBLIC