

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,203-0000

LEASE NAME Chalk

WELL NUMBER 1-28

SPOT LOCATION SW NW SE

SEC. 28 TWP. 24 SRGE. 17 (~~XXX~~(W))

COUNTY Edwards

Date Well Completed 9-8-84
10:15 PM,

Plugging Commenced 9-7-84

12:05 AM,
Plugging Completed 9-8-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4585'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	255'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. Heavy mud through open ended drill pipe. 50
sacks at 1170'; 70 sacks at 500'; bridge, 1 sack hulls, plug ant 10 sacks
at 40'. 15 sacks in rathole with joint of pipe. Pulled water well and plugged with
5 sacks. Used 60/40 Pozmix, 2% gel(4% total) + 3% cc.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner

(employee of operator) or SEP 17 1984

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F. A. Wuellner
(Address) F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas
67579

SUBSCRIBED AND SWORN TO before me this 10th day of September, 1984.

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- CHALK #1-28

Located: SW NW SE, Section 28-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 1, 1984

COMPLETED: September 8, 1984

TOTAL DEPTH: 4585'

LOG

0 - 90 Surface Soil and Sand
 90 - 258 Clay, Shale
 258 - 1150 Shale, Sand, Red Beds
 1140 - 1175 Shale
 1175 - 1196 Anhydrite
 1196 - 1675 Shale, Lime Stringers
 1675 - 4500 Lime and Shale
 4500 - 4585 Lime

CASING RECORD

Ran 6 joints new 8 5/8", 23# casing.
 243.42' pipe set at 255' K.B.
 Cemented with 210 sacks 60/40 Pozmix
 with 3% cc. Plug down at 4:30 PM,
 9-1-84, by Howco.

Plugged.

Deviation Surveys: 1° at 2099'
 1 1/2° at 4460'

RECEIVED
 STATE CORPORATION COMMISSION

SEP 17 1984

CONSERVATION DIVISION
 Wichita, Kansas