

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,180-0000

LEASE NAME Hoar

WELL NUMBER 1-29

SPOT LOCATION NE SW NW

SEC. 29 TWP. 24 RGE. 17 (W)

COUNTY Edwards

Date Well Completed 5-30-84
6:00 PM,

Plugging Commenced 5-30-84
7:15 PM,

Plugging Completed 5-30-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl
ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? _____ Dist. # 1

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 4617'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	270'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Filled hole with heavy mud.

Plugged with 50 sacks at 1160'; 40 sacks at 530';

50 sacks at 320'; plug and 10 sacks at 40'.

15 sacks in rathole. Used 60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579


STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1984

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
(Address) P. O. Box 129, Sterling, Kansas 67579



CONSERVATION DIVISION
SUBSCRIBED, AND SWORN TO before me this 31st day of May, 1984

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HOAR #1-29

Located: NE SW NW, Section 29-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 24, 1984

COMPLETED: May 30, 1984

TOTAL DEPTH: 4617'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints 8 5/8" casing. 257.66'
90 - 273 Clay - Shale	pipe set at 270' K.B. Cemented with
273 - 1060 Shale, Sand, Red Beds	225 sacks 60/40 Pozmix, 2% gel and
1060 - 1168 Shale, Lime Stringers	3% cc. Plug down at 5:15 PM, 5-24-84,
1168 - 1187 Anhydrite	by Howco.
1187 - 1715 Shale	
1715 - 4617 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 2150'
1 3/4° at 4493'

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1984

CONSERVATION DIVISION
Wichita, Kansas