

WELL PLUGGING RECORD


STATE OF KANSAS STATE-CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Stafford County. Sec. 5 Twp. 24S Rge. 13 (E) W. (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW SE Lease Owner Crown Oil Company, Inc. Lease Name Smith Well No. 1 Office Address Odell at Tenth, Great Bend, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed November 6 19 49 Application for plugging filed November 6 19 49 Application for plugging approved November 6 19 49 Plugging commenced November 6 19 49 Plugging completed November 7 19 49 Reason for abandonment of well or producing formation... If a producing well is abandoned, date of last production... 19... Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough Producing formation... Depth to top... Bottom... Total Depth of Well... Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. The table is currently empty.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to ... feet for each plug set.

4138' to 323' with heavy rotary mud 1 plug with 15 sacks 323' to 45' heavy rotary mud 45' to surface plug with 10 sacks

11-10-49

RECEIVED Conservation Division NOV 10 1949 STATE CORPORATION COMMISSION KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Crown Oil Company, Inc. Address Box 164, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss. H. R. Buick (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Buick St. John, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 8th day of November, 19 49

Edwina Elder Notary Public.

My commission expires September 21, 1953.

PLUGGING FILE SEC 5 T 24 R 13 W BOOK PAGE 123 LINE 25

DRILLER'S LOG

COMPANY: CROWN OIL COMPANY, INC. LOCATION: NW NW SE 5-24S-13W
 CONTRACTOR: HILTON DRILLING COMPANY, INC. Stafford County, Kansas
 FARM NAME: SMITH NO. 1 ELEVATION: 1915 DF
 COMMENCED: 10-18-49
 COMPLETED: 11-6-49

CASING USED: 8-5/8" at 323' with 175 sacks

Cellar	5
Sand and Shale	100
Shale	130
Sand	155
Shale	205
Shale and Shells	323
Shale and Red Bed	655
Shale and Shells	790
Anhydrite	820
Shale	1030
Shale, Shells and Salt	1335
Shale and Shells	1705
Shale and Lime	1995
Lime and Shale Streaks	2125
Lime and Shale	2190
Lime Shells and Shale	2260
Lime and Shale	2390
Shale and Shells	2635
Lime and Shale	2760
Shale and Shells	2850
Lime and Shale	3375
Lime	3520
Lime and Shale	3570
Lime	3880
Chert	3912
Chert and Lime	3920
Shale	3935
Chert	3559
Chert and Shale	3981
Lime	4011
Lime and Chert	4015
Chert and Shale	4025
Chert	4042
Chert and Shale	4070
Shale	4100
Lime	4138
Total Depth	4138

RECEIVED
 NOV 10 1949
 STATE OF KANSAS
 COMMISSION
 KANSAS

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

PLUGGING
 FILE SEC 5 T 24 R 13W
 BOOK PAGE 183 LINE 25

CROWN OIL COMPANY, INC.

W. R. Deuch

Subscribed and sworn to before me this 8th day of November, 1949.

My commission expires September 21, 1953.

Edwina Elder
 Notary Public