


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Kingman County, Sec. 20 Twp. 28 Rge. (E) 5 (W)

Location as "NE/CNW/SW" or footage from lines. SE SE NE  
Lease Owner Earl F. Wakefield  
Lease Name Moorehouse "B" Well No. 2  
Office Address 307 Union Nat'l Bank Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 1 19 53  
Application for plugging filed June 1 19 53  
Application for plugging approved June 1 19 53  
Plugging commenced June 2 19 53  
Plugging completed June 2 19 53  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 118.15 | None       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from 3883 feet to 125 feet, bridged with wood plug & 1/2 Sack Hulls, Cemented with 15 sacks, filled with heavy mud to 20 feet below bottom of cellar, Bridged with wood plug & 3/4 sack hulls, Cemented to bottom of Cellar with 5 sacks.

STATE CORPORATION COMMISSION

JUN 16 1953 06-06-53

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Earl F. Wakefield  
Address 307 Union Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Earl F. Wakefield (Employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield  
307 Union Nat'l Bank Bldg.  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1953

My commission expires 12-23-54



15-095-01544-0000

Moorehouse "B" #2  
Owner: Earl F. Wakefield  
Contractor: Earl F. Wakefield  
Comm: 5/20/53 Comp: 6/1/53

SE SE NE 20-28S-5W  
Kingman County, Kansas  
Casing: 125' of 8 5/8"

Elevation: 1402 D.F.

|                    |      |
|--------------------|------|
| Red & Gray Keel    | 85   |
| Sandy Shale        | 90   |
| Shale & Shells     | 915  |
| Sandy Lime         | 1070 |
| Sandy Shale        | 1110 |
| Sandy Lime & Shale | 1550 |
| Shale & Shells     | 1715 |
| Lime & Shale       | 2170 |
| Sandy Shale & Lime | 2200 |
| Lime & Shale       | 2800 |
| Lime               | 2840 |
| Lime & Shale       | 3019 |
| Lime (K.C.)        | 3100 |
| Lime & Shale       | 3665 |
| Sandy Shale & Lime | 3700 |
| Shale & Lime       | 3790 |
| Shale              | 3822 |
| Lime (Mississippi) | 3883 |

STATE OF KANSAS )  
                          ) ss  
COUNTY OF SEDGWICK )

I hereby agree and certify that the above is a true and correct copy of the log on the Moorehouse "B" #2 well located SE SE NE 20-28S-5W, Kingman County, Kansas.

Earl F. Wakefield

Sworn and subscribed before me this 2nd day of June, 1953.

J. Jerome Gaffney

My Commission Expires: 12-23-54

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 6 1953  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 20 28 N 5W  
BOOK PAGE 16 LINE 18