


15095-017400000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 20 Twp. 28 Rge. 5 (E) (W)
Location as "NE/CNW/SW" or footage from lines. SE NE NE
Lease Owner Earl F. Wakefield
Lease Name Morehouse Well No. B-1
Office Address 515 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 9-09 19.51
Application for plugging filed 11-08 19.63
Application for plugging approved 11-10 19.63
Plugging commenced 11-11 19.63
Plugging completed 11-13 19.63
Reason for abandonment of well or producing formation deleted

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3862 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	120	circulated
				5 1/2	3878	2978.53

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with chat from 3843 feet to 3800, dumped 5 sacks cement
Filled hole with mud to 235 feet, set 15 foot rock bridge
Dumped 30 sacks cement.
Mud hole to 40 feet, set 5 foot rock bridge and dumped 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1963 11-21-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering & Construction Co.
Address Box 342, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mary Payne
El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19.63

My commission expires Sept 27, 1967

Ronald R. Thomas
Notary Public.

15-095-01740000

Moorhouse B #1
Owner: Earl F. Wakefield
Contractor: Earl F. Wakefield
Comm: 8-30-51 Comp: 9-9-51

SE NE NE
20-28S-5W
Kingman County, Kansas
Casing: 120' of 8 5/8"
3878' of 5 1/2"

Elevation 1396

Surface	125
Shale & Shells	1030
Shale & Lime	3055
Lime	3115
Lime & Shale	3213
Lime	3600
Lime & Shale	3804
Lime & Chert	3835
Dolomite	3845
Rotary Total Depth	3845

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the Moorhouse B #1 well located SE NE NE, 20-28S-5W, Kingman County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 19th day of September, 1951.

W. O. [Signature]

My Commission Expires: 12-23-54