

15-095-01857-000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kingman County, Sec. 20 Twp. 28 Rge. 5 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE SW NW

Lease Owner Maurice L. Brown  
Lease Name Moorehouse A. Well No. 1  
Office Address 1500 Vickers KSB&T Bldg., Wichita, Kan. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Oil  
Date Well completed 19  
Application for plugging filed 4-4- 19 77  
Application for plugging approved 4-4- 19 77  
Plugging commenced 5-9- 19 77  
Plugging completed 1:30 5-13- 19 77  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Buddy Metz  
Producing formation Depth to top Bottom Total Depth of Well 3929  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	272	None
				5 1/2	3928	3125

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand from 3920 to 3858'  
5 sacks cement from 3858 to 3835'

Wooden bridge at 300'  
Rock from 300 to 290'  
5 yards ready mix to surface

RECEIVED  
STATE CORPORATION COMMISSION

RECEIVED

JUL 21 1977

07-21-77

CONSERVATION DIVISION  
WICHITA, KANSAS

08-02-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Don Hicks (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

200 Sutton Place (Address) Wichita, Kans  
1st day of August, 19 77 67202

Marjorie P. Jennings Notary Public.

My commission expires July 29, 1981

SUBSCRIBED AND SWORN TO before me this



1509501857-0000

ROTARY DRILLING LOG

OPERATOR: Leslie Oil Company  
MOORHOUSE "A" NO. 1  
SE SW NW Sec. 20-28S-5W,  
Kingman County, Kansas

CONTRACTOR: Prime Drilling Company  
COMMENCED: 8-21-61  
COMPLETED: 9-2-61

Remarks: Set 8-5/8" surface casing  
at 272' cemented with 200  
sacks HA-5

Formations:

Sand	45'
Shale & Shells	65'
Shale	375'
Shale & Salt	790'
Anhydrite	940'
Lime & Shale	1160'
Shale & Lime	1315'
Lime	1480'
Lime & Shale	1674'
Shale & Lime	1875'
Lime & Shale	1980'
Lime	2110'
Lime & Shale	2190'
Shale & Lime	2230'
Lime & Shale	2345'
Shale & Lime	2625'
Lime & Shale	2775'
Shale & Lime	2945'
Lime & Shale	3162'
Shale & Lime	3255'
Lime	3525'
Lime & Shale	3579'
Lime	3745'
Lime & Shale	3829'
Lime	3873'
Core #1	3890'
Lime	3929'
Rotary Total Depth	3929'

Set 5-1/2" casing at 3928' cemented  
with 100 sx. Pozmix.

We certify the above log is true  
and correct to the best of our  
knowledge and belief.

PRIME DRILLING COMPANY

*R.R. McNicol*

R. R. McNicol