

15-095-20428-000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217


Locate well correctly on above  
Section Plat

Kingman County, Sec. 20 Twp. 28S Rge. 5 (X) (W)  
 Location as "NE/CNWSW" or footage from lines C SE NW SE  
 Lease Owner: Graves Drilling Co., Inc.  
 Lease Name: Dewey Well No. 1  
 Office Address: 910 Union Center  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed: October 7, 19 75  
 Application for plugging filed: October 7, 19 75  
 Application for plugging approved: October 7, 19 75  
 Plugging commenced: October 7, 19 75  
 Plugging completed: October 7, 19 75  
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas  
 Producing formation Depth to top Bottom Total Depth of Well Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	216	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 35 sacks cement thru drill pipe to 200'. Followed by wooden plug and 1/2 sack hulls. Pumped 15 sacks cement thru drill pipe to 40' followed by wooden plug, 1/2 sacks hulls to base of well cellar. Plugged rat hole

RECEIVED  
STATE CORPORATION COMMISSION

OCT 15 1975

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor: Graves Drilling Co., Inc. (If additional description is necessary, use BACK of this sheet)  
 Address: 910 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Secgick ss.  
 John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
 910 Union Center, Wichita, Kansas 67202  
 (Address)

Subscribed and Sworn to before me this 13th day of October 19 75

My commission expires May 9, 1979 Betty Brandt Notary Public

15095-20428-0000

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: September 29, 1975  
910 Union Center  
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: October 7, 1975  
910 Union Center  
Wichita, Kansas

CASING RECORD: Ran 5 Jts. of 8-5/8" @ 216' LOCATION: Dewey No. 1  
cemented with 160 sacks C SE NW SE  
Section 20-28S-5W  
Kingman County, Kansas

-----

0 - 216	Red bed & gravel
216 - 310	Shale
310 - 975	Shale & shells
975 - 1305	Shale, shells & lime
1305 - 1625	Shale
1625 - 1866	Shale & lime
1866 - 2530	Lime shale & sand
2530 - 2745	Shale & lime
2745 - 2965	Shale
2965 - 3500	Shale & lime
3500 - 3738	Lime
3738 - 3845	Lime, shale, and iron pyrite
3845 - 3915	Lime
3915	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 15 1975  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves*  
President

STATE OF KANSAS )  
                          ) SS  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 13th day of October, 1975

My commission expires: May 9, 1979

*Betty Brandt*  
Betty Brandt Notary Public